

## DEMOLITION

**GENERAL:** Provide DEMOLITION to the extent indicated.

**QUALITY ASSURANCE:** All demolition shall be in strict compliance with applicable codes and standards, including local ordinances regulating noise, air pollution, waste disposal and public safety. COORDINATE all work with requirements of new construction.

**PROTECTIONS:** Provide barricades or other forms of protection as required to protect workers and general public from injury due to demolition work. Provide SHORING, BRACING, or SUPPORT to prevent movement, settlement, or collapse of structure to be demolished and/or adjacent facilities to remain.


**UTILITIES:** Locate, identify, stub off, and disconnect utility services that are not indicated to remain.

**SALVAGE:** Where indicated, store items on site for reincorporation into the project or removal by OWNER. Protect salvaged items from damage from demolition operations, weather, theft, and other hazards.

**REMOVAL:** Items indicated to be removed, but of salvageable value to the Contractor may be removed from structure as work progresses. Transport salvaged items from site as they are removed. Storage or sale of removed items on site will not be permitted.

**DISPOSAL:** Remove debris, rubbish and other materials resulting from demolition operations from building site. Transport and legally dispose of materials off site.


**CLEAN-UP & REPAIR:** Upon completion of demolition work, remove tools, equipment and demolished materials from site. Remove unneeded protections and leave work areas broom clean. Repair demolition performed in excess of that required. Return structures and surfaces to remain to condition existing prior to demolition.



EXPLORATORY DEMOLITION plan

117 Broadway, Chico, Ca

1720 07.17.2012



**GRIFFITH ARCHITECTS**  
ARCHITECTURE | ENGINEERING | INTERIORS

242 BROADWAY SUITE 8 CHICO CALIFORNIA 95928 530.343.4621 GRIFFITHARCHITECTS.COM

